



TEMPORARY
HUMIDITY CONTROL

Construction Heating and Cooling



Property Damage
Restoration



Temporary
Humidity Control



Property Damage
Prevention



APPLICATION

Overview

The ability to keep a construction project on schedule is detrimental to its ability to provide profit to both the contractor and owner of the building. Temperature issues at the project site can be chief contributors to delays in the schedule completion and to potential damage of materials at the site. The need to provide a comfortable environment for workers is also necessary in areas where temperatures can reach well below freezing.

The need to provide temporary climate control solutions during summer and winter applications is essential to ensuring that your construction projects are completed to standard and on time. Munters can supply state-of-the-art temporary indirect fired heaters and cooling units for every construction need. Whether it is for worker comfort or drying paint, these technically advanced pieces of equipment are designed to provide an efficient, cost effective means for completing any project.

Temporary temperature control is vital during times of year when conditions can fluctuate within extremes. Risks from mould growth, broken pipes, frozen paint, dry wall compound not drying and other temperature dependent issues can be avoided by utilising a temporary climate control regiment.

In the winter, Munters provides indirect fired heaters designed to provide warm, clean air. This means that a project will not only stay on schedule but the space remains free from harmful carbon monoxide fumes. In the summer, Munters provides ultra efficient cooling units to provide the necessary cooling to keep workers comfortable while providing basic conditions for mould reduction and the drying of coatings.



A simple, precise way of controlling humidity.



TEMPORARY
HUMIDITY CONTROL

Construction Heating and Cooling



PROCEDURE

In order to ensure that the equipment is tailored specifically to each construction project, the following requirements are necessary:

- Size of the room
- Location and number of all envelope openings
- Product specifications
- Site logistics
- Weather conditions
- Electrical source and location.

Only when this information is compiled and analysed can the suitable equipment be selected. Munters personnel then engineer the equipment for specific applications to meet the desired specifications and to avoid contamination.

Munters technicians' service and check the equipment, ducting and ancillary items prior to delivery. It is vital that the heating and cooling equipment and ducting is clean to eliminate the threat of contamination. The equipment is then placed in a designated area, positioned close to a power supply and set up to maximise the safe operation of the unit.

Munters state-of-the-art desiccant dehumidification systems are utilised to treat the ambient air in the structure ensuring that the materials are protected, the workers are safe and the project stays on schedule. Munters provides a turnkey solution with well engineered equipment, offering around the clock service that is unmatched in the industry.



Munters global fleet of equipment can be mobilised within hours.



RESULTS

Munters experienced and highly trained staff can consult customers on the best solutions for their specific needs. By utilising Munters state-of-the-art climate control equipment, conditions are closely controlled to maintain relative humidity, dew point and temperature through out the facility. Munters advanced heating and cooling solutions eliminates the risks of problems caused by extreme cold or hot weather conditions, while maintaining construction schedules.



Custom designed solutions to meet the needs of each client.

BENEFITS

- Energy cost savings, incorporating environmentally-friendly technology
- Maintain tight construction schedules
- Increased project quality
- Improve productivity by providing comfortable working conditions
- Improve indoor air quality
- Around the clock technical services
- Eliminates mould growth
- Minimises material related warranty issues due to temperatures.



Munters equipment maintains construction schedules.